



Satyawati College

सत्यवती कॉलेज

ASHOK VIHAR, PHASE-III, DELHI-110052

अशोक विहार, फेज-III, दिल्ली-110052

Website : www.satyawati.du.ac.in, E-mail : principal@satyawati.du.ac.in



Fax / फ़ैक्स : +91-27446953, Phone / फ़ोन : +91-11-27240406, +91-11-27219570

NAAC ACCREDITED "A" GRADE

Dated: 16.12.2020

NOTICE INVITING TENDER

Satyawati College invites quotation from reputed & eligible agencies for **Making provision of locating the fault by fault locating machine and S/F of 3½ X 50 sqmm cable for restoring the supply** at Satyawati College, Ashok Vihar, Phase-III, Delhi. Notice Inviting Quotation documents are attached.


(Dr. Nirmal Jindal)
Acting Principal


Encl: As above

Copy to:

1. Convener, Auditorium & Seminar Committee
2. P.A. to Principal (Evening)
3. Administrative Officer (Morning/Evening)
4. Section Officer (Admin.)
5. College website
6. Delhi University website
7. Engineering Department, Delhi University

Page 1 of 3

NOTICE INVITING QUOTATION

Date: 16/12/2020

Satyawati College invites quotation from reputed & eligible agencies for **Making provision of locating the fault by fault locating machine and S/F of 3½ X 50 sqmm cable for restoring the supply** at Satyawati College, Ashok Vihar, Phase-III, Delhi.

Name of work: Making provision of locating the fault by fault locating machine and S/F of 3½ X 50 sqmm cable for restoring the supply at Satyawati College, Ashok Vihar, Phase-III, Delhi.

Estimated Cost: Rs.29,680/-

Time period for completion of the work: 14 days from the seventh day of issue of award letter/work order.

Date of receiving of tender document upto: 06.01.2021 at 2:30 p.m.

Date of opening tender document: 06.01.2021 at 3:30 p.m.

Tender opening/receiving authority: Principal, Satyawati College, Ashok Vihar, Delhi

Undertaking:

I/We hereby quote item rate _____ as par on the estimated cost of Rs.29,680/-

Signature of Contractor


Signature of Principal

I/We hereby undertake our agency have not been black listed/debarred in any government/semi-government organization since last three years.

Signature of Contractor

Conditions:

1. No conditional tender will be accepted
2. College authority reserves the right to accept or reject any or all tenders without assigning any reason thereof.
3. Rate quoted will be in figure and words.
4. No deviation/extra item/substitute item shall be carried out without the approval/sanctioning of the competent authority.
5. Payment will be made after due satisfaction of competent authority.
6. Taxes as applicable from time to time will be deducted from the gross amount of bill.
7. The material used in the work got approved from the competent authority. Without sample approval the work seems to be rejected and no payment will be made for.
8. The tender papers will be considered with relevant documents like registration of contractor, PAN card, GST.

Estimate

Sub: Making provision of locating the fault by Fault locating machine and S/F of 3½ X 50 sqmm cable for restoring the supply at Satyawati Collage, University of Delhi.

S. No	Item Code	Description of Items	Qty	Unit	Rate	Amount
1		Finding and detecting location of underground LT cable with FLC machine including excavation, pin pointing, fault, refilling after repair of ground at marked fault as required at site.	1	job		
2	MR	Supplying , fixing and laying of one number PVC insulated and PVC sheathed /XLPE aluminium armoured conductor power cable conforming to 1.1 KV grade of following size direct in ground including excavation, sand cushioning , protective covering ,refilling the same etc as reqd. 3½ X 50 sqmm	10	mtr		
3		Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required				
a	MR	3½ X 50 sqmm	2	each		
4	MR	Making arrangement of excavation the road by mechanical or machine after digging out the trench for laying of suitable size of cable etc as reqd at site by Engineer-in-charge .	10	mtr		
5	MR	Repairing the same after excavation the road with cement concrete of suitable size including disposal the excavated road material and soil to be levelled and nealty dressed etc as reqd. at site.	1	job		

Total

Specific make:-

- | | | |
|---|------------|------------------------------------|
| 1 | Wire/cable | : Havells/Skytone/Grandlay/Polycab |
| 2 | Pole box | :-Syntex |
| 3 | Fitting | : crompton/Havells |